/000

# ENGINEERING DEPARTMENT.

## BNNGALORE DIVISION.

*Dated 8th November* 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., of 30th November 1930, for Restoring Isthur Hosahally Minor tank Register No. 101, of Hoskote taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. (*a*) Tenders quoting percentages above or below estimate will be rejected.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Restoring Isthur Hosahally Minor tank, Register No. 101 of Hoskote Taluk, in default of which tenders will be rejected."

5. The final acceptance of tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board of the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted against each item of work both in words and figures.

Restoring Isthur Hosahally tank, Register No. 101, of Hoskote Taluk.

| No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | *Bund R. L. 60·00 top width 4' feet at Breach 6'.* | | Rs. a. p. | | |
| 1. | Earthwork to bund including watering and tamping. | C.yds. | | 3,007 | |
| 2 | Earthwork to bund breach filling ... | ,, | | 899 | |
| 3 | Puddle wall mixed with gravel ... | ,, | | 151 | |
| 4 | Stone pitching 3/4" thick ... ... | S.yds. | | 182 | |
| 5 | Turfing ... ... ... | ,, | | 5,250 | |
| 6 | Providing necessary grade stones with figuring and painting. | Each | | 20 | |
| 7 | Do Index stones ... | ,, | | 20 | |
| 8 | Do Registered No. stone | ,, | | 1 | |
| 9 | Do Gauge stone ... | ,, | | 1 | |
| 10 | Removing and refixing B. M. stones ... | ,, | | 2 | |
| | *Sluice.* | | | | |
| 1 | Repairing the existing sluice including locking arrangements, etc., complete. | Lump | | sum | |
| | *Waste Weir left at 54·50 and 80' long.* | | | | |
| 1 | Earthwork excavation and used to training bank. | C.yd. | | 391 | |
| 2 | Burnt brick in surki mortar ... ... | C.ft. | | 194 | |
| 3 | Burnt stone slabs 6" thick roughly dressed and fixed. | S.ft. | | 112 | |
| 4 | Plastering with surki mortar .. ... | Sqr. | | 2·00 | |
| 5 | Rough stone work new ... ... | C.yd | | | |

*Abstract Notification.*

The attentation of the public is drawn to the *Mysore Gazette*, Notification No. 14-29, dated 13th November 1930, for extending the Chief Commandant's Office at Hebbal, the last date of receipt of tender is 25th November 1930. Earnest money required is Rs. 200.

N. G. KRISHNAIENGAR,
*Executive Engineer.*

## KOLAR DIVISION.

*Notice dated 28th October 1930.*

The attention of the public is invited to the Notification published in the *Mysore Gazette* Part VI, pages 1377 and 1378, calling for tenders for Resorting Thimmnahalli Kanivekere Reg. No. 858, Bagepalli Taluk.

The latest date for tender is 25th November 1930.

N. LAKSHMINARASIMHAIYA,
*Executive Engineer.*

## TUMKUR DIVISION.

*Abstract Notification.*

Restoring Bommenahalli-Dasanakatte Tank, Regd. No. 207 of Madhugiri Taluk, Tumkur District.

Attention of the public is drawn to the notification calling for tenders for the above work in pages 1433 and 1434, Part VI of the *Mysore Gazette*, dated 13th November 1930.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 3 P.M. of 24th November 1930.

3. An earnest money of Rs. 300 should accompany the tender.

---

*Dated 6th November 1930.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 5 P.M. of 2nd December 1930, for "Restoring Haresandra Machikatte Tank, Registered No. nil of Tiptur Taluk, Tumkur District." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of September 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government promissory notes, as earnest money and be superscribed "Tender for Restoring Haresandra Machikatte Tank, Registered No. nil of Tiptur Taluk, Tumkur District" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore, who does dot bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender of the successful competitor will be required to execute the usual bond in default of which his tender will be cancelled and earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer, will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump